BRUHAT BANGALORE MAHANAGARA PALIKE

MODIFIED APPROVED SCHEDULE - B

Name of the Work : Improvements to Roads and Drains at Ramachandrapura Old village, Hanuman Layout, Anjaneya Temple and Satya Narayana Temple surroundings in Ward No. 10 Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Rates of KRIDL	
				In Figures	In Words
1	101.00	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	90.72	Rupees Ninety and Seventy Two Paise Only
2	202.00	KSRRB M300-53: Construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum watering charges & compaction by vibratory	Cum	163.24	Rupees One Hundred Sixty Three and Twenty Four Paise Only
3	151.50	Providing and laying in position **plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs** using **40mm** and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, **in foundation and plinth**, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of	Cum	4290.84	Rupees Four Thousand Two Hundred Ninety and Eighty Four Paise Only
4	101.00	KSRRB M2600-3: Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification	M	137.16	Rupees One Hundred Thirty Seven and Sixteen Paise Only
5	151.50	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	Cum	6464.88	Rupees Six Thousand Four Hundred Sixty Four and Eighty Eight Paise Only
6	1010.00	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift	Sqm	91.80	Rupees Ninety One and Eighty Paise Only
7	95.95	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	72.71	Rupees Seventy Two and Seventy One Paise Only

Signature of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92